

Remove existing fence around perimeter of proposed MUGA and investigate costs of replacing remaining fence

Install 2.0m galvanised steel weldmesh fence panels around remainder of MUGA

Install 5.0m galvanised steel weldmesh fence panels along boundary with car park

Overlay existing surface with bitmac wearing course

Provide and lay 50 x 150mm pcc edgings

Remove existing steel tennis fence. Relocate ball court fence to new position in between new ball court and existing tennis court

Relocate goal posts from former football pitch to new location

Install goal posts, basketball ring, backboard and post

Provide line markings to new MUGA and newly relocated ball court

KEY:

- Proposed Bitmac Surface
- Proposed Weld Mesh Fence

