

KEY:




FOOTWAY CONSTRUCTION

AC 6 Dense Surf 100/150, 20mm depth

AC 20 Dense Bin 100/150, 60mm depth

Type 1 stone sub-base, 200mm depth



Proposed pcc edgings



Existing vegetation (cut back)

CHAPMAN COURT

Excavate existing grass surface and
replace with new footway construction
as per LCC specification

Retain new construction with
pcc edgings along existing
fence

Cut back/remove vegetation
encroaching on area to be
surfaced

Remove existing pcc edgings and
provide stepped joint between
existing and new footway
construction

Borough of Pendle Housing, Health and Engineering Services
Town Hall, Market Street, Nelson. BB9 7LG
Tel: (01282) 661661 www.pendle.gov.uk

PROJECT:
Chapman Court,
Barnoldswick

TITLE:
Verge Hardening:
Proposed Works

STATUS:
Preliminary

PROJECT REF:
ENG101

DRAWING NUMBER:
E0807D / 2

SCALE:
1 : 100 @ A1

DESIGNED:
N Y

CHECKED:
ScW

DATE:
Mar 2022